

06 10 00 - Rough Carpentry

Provide backing in areas where equipment will be installed on walls. Confirm locations with Project Manager.

Provide backing in additional areas where equipment may be installed on walls in the future. Provide minimum 20 gage steel studs at 16 inches on center.