

05 41 00 - Structural Metal Stud Framing

Provide backing in area where equipment will be installed on walls. Contractor shall coordinate all locations with subcontractors. Provide backing in additional areas where equipment may be installed on walls in the future. Provide minimum 20 gage steel studs at 16 inches on center. Confirm art installations, or potential locations with University Project Manager prior to installing.